5. Every tenderer must deposit in any of the Mysore Government Treasuries as earnest money a sum of Rs. 50, and forward the receipt obtained therefor with his tender. Firms outside the Mysore Province, may, however, remit the money to this office direct.

6. The name of the successful tenderer will be notified in due course on the board at the Chief Commandant's Office and he will be required to deposit as security one-tenth of the value of the article to be supplied and to execute an agreement for the due fulfilment of the contract for the supply required within a week from the date of acceptance of tender.

7. Should the contractor fail to comply with any of the conditions detailed above, the contract will be forthwith cancelled, and the deposit credited to Government.

8. The Chief Commandant reserves to himself the right of accepting or rejecting any tender without assigning any reason therefor.

Name of articles.	*Approximate quantity.*
(1) Cloth Heather mixture 54" wide	... 154 yards.
(2) Large buttons	... 65 dozens.

C. A. H. P. LANDON,
Chief Commandant.

TENDER FORM.

To

The Chief Commandant,
Mysore State Troops, Bangalore.

$\frac{\text{I}}{\text{we}}$ offer to supply the article according to the sealed sample at the Military Stores at the rates given in the accompanying list. It will be delivered at the Military Stores within two weeks from the date of communication of acceptance of tender.

Yours faithfully,

Dated..... .....

MYSORE RAILWAYS.

Notificatin dated 10th November 1928.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Mysore Railways, Hassan, up to 1st December 1928, till 5 P.M., for constructing a new station building at Hampapura and Lalandevanhalli. An approximate estimate of quantities of the two buildings is given in the following schedule separately. The quantities are not guaranteed. The work should be completed by the end of April 1929, showing continuous equal monthly progress.

2. Plans, detailed estimate and conditions of schedule agreement, may be seen at the Executive Engineer's Office at Mysore Railways, Hassan, on all working days between 11 A.M. and 5 P.M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer, on payment of one rupee. Separate forms have to be used for the two works.

4. Each tender must be accompanied by a deposit of rupees one hundred (Rs. 100) in cash or Government Promissory Notes, as earnest money, and should be superscribed "TENDERS FOR CONSTRUCTING A NEW STATION BUILDING AT..... STATON", in default of which tenders will be rejected.

5. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned early.

2. The final acceptance of any tender will rest with the Engineer-in-Chief, Mysore Railways, Mysore, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

7. The name of the competitor, whose tender has been accepted, will be posted on the Notice Board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will be answered.

8. Within eight days of the acceptance of the tender, the successful competitor is required to execute the usual schedule agreement in the form prescribed, in default of which his tender will be considered cancelled.

SCHEDULE.

For constructing a Pucca Station Building at Hampapura on Mysore-Arsikere Railway.

No.	Items of work	Unit	Quantity	Rate
1	Earthwork excavation for foundations ...	1,000 C.ft.	2,400	
2	Concrete broken stone in mortar	100 C.ft.	820	
3	Size stone in mortar in foundations	,,	550	
4	Burnt brick in mortar	,,	800	
5	Do mud	,,	2,000	
6	Do arch work in mortar	,,	60	
7	Burnt stone slabs 6" thick dressed and fixed ...	S.ft.	201	
8	Cut stone work	C.ft.	28	
9	Plastering with mortar	Sqr.	4,400	
10	White and colour washing	100 S.ft.	4,400	
11	Gateway C. I. with hinges, bolts, etc., complete ...	No.	1	
12	Iron hand railing including painting and fixing ..	,,	1	
13	Teakwood doors panelled with frames, fittings, etc., complete (1½" thick).	S.ft.	25	
14	Teakwood battened doors with frames, fittings, etc., complete (1½" thick).	,,	42	
15	Teakwood glazed windows and vintilators inculding fixing, etc., complete with iron bars (1¼ inch thick).	,,	24	
16	Teakwood windows pannelled with frames, fittings, iron bars, etc., complete (1¼" thick).	,,	18	
17	Teakwood ticket window with frames, fittings, etc., complete.	,,	16	
18	Brackets of angle and T. iron as shown in drawing No. 119—1928, Enc. including *tie* rods, fixing charges, etc., complete.	No.	5	
19	Teakwood stand for ticket window including fixing in position.	S.ft.	16	
20	Teakwood king post trusses of 16 feet span with iron straps, bolts, hoisting, fixing, etc., complete.	No.	2	
21	Rails 41¼ lbs. section F. F.	R.ft.	40	
22	Fixing rails in position, ...	,,	40	
23	Teakwood shelves of plank 1½" thick with brackets, fixing, painting, etc., complete.	S.ft.	100	
24	Teakwood cupboard with doors, hinges, hasps, staples, painting, etc., complete.	,,	12	
25	Teakwood wrought and put up including wood oiling.	C.ft.	96·92	
26	Roofing with first class Mangalore tiles over teak reapers 2" x 1" with chunam borders, etc., complete.	100 S.ft.	1,760	
27	Mangalore ridge tiles set in mortar	R.ft.	40	
28	Flooring with Cuddapah slabs 1½" thick over 4" concrete including cement pointing, etc., complete.	100 S.ft.	740	
29	Teakwood eave board 9" x ¾" ornamental including painting, etc, complete.	R.ft.	170	
30	Finials of teakwood, large, including fixing and painting.	No.	2	
31	Painting with silicate paint, two coats ...	100 S.ft.	300	
32	Teakwood barge board	S.ft.	10	
33	Glass tiles	No.	10	
34	Providing cement boards on walls of waiting room with borders, etc., complete.	Lump sum		
35	Railway freight on gate and railing	Lump sum		
36	Teakwood benches 6 feet long	No.	2	
37	Levelling ground	Lump sum		

SCHEDULE—*concld.*

For constructing a Pucca Station Building at Lalandevanhalli on Mysore-Arsikere Railway.

No.	Items of work	Unit	Quantity	Rate
1	Earthwork excavation for foundations	1,000 C.ft.	14,000	
2	Concrete broken stone in mortar	100 C.ft.	820	
3	Size stone in mortar in foundations	,,	550	
4	Burnt brick in mortar	,,	800	
5	Do mud	,,	2,000	
6	Do mortar—Arch work	,,	60	
7	Burnt stone slabs 6" thick dressed and fixed ..	S.ft.	201	
8	Cut stone work	C.ft.	28	
9	Plastering with mortar	100 S.ft.	4,400	
10	White and colour washing	,,	4,400	
11	Gateway of C. I. including hinges, bolts, etc., complete.	No.	1	
12	Iron hand railing including painting and fixing ...	,,	1	
13	Teakwood panelled doors (1/2" thick) with frames, fittings, etc., complete.	S.ft.	25	
14	Teakwood battened doors (1/2" thick) with frames, fittings, etc., complete.	,,	42	
15	Teakwood windows glazed with iron bars and glazed ventilators including fixing, etc., complete (1¼" thick).	,,	24	
16	Teakwood windows panelled with frames, fittings, iron bars, etc., complete (1¼" thick).	,,	18	
17	Teakwood ticket windows with frames, fittings, etc., complete.	,,	16	
18	Brackets iron including *tie* rods as per drawing No. 119—1928 ENC. including fixing charges.	No.	5	
19	Teakwood hand stand (barricading) in front of ticket window including fixing in position.	S.ft.	16	
20	Teakwood king post trusses of 16 feet span with iron straps, bolts, hoisting, fixing, etc., complete.	No.	2	
21	Rails 41½ lbs. section F. F.	R.ft.	40	
22	Fixing rails in position	,,	40	
23	Teakwood shelves of plank 1½" thick with brackets, fixing, painting, etc., complete.	S.ft.	100	
24	Teakwood cupboard with doors, hinges, hasps, staples, paintings, etc., complete	,,	12	
25	Teakwood wrought and put up including wood oiling.	C.ft.	96·92	
26	Roofing with first class Mangalore tiles over teak reepers 2" x 1" with chunam borders, etc., complete.	100 S.ft.	1,760	
27	Mangalore ridge tiles set in mortar	R.ft.	40	
28	Flooring with Cuddapah slabs 1½" thick over 4" concrete including cement pointing, etc., complete.	100 S.ft.	740	
29	Teakwood eave board 9" x ¾" including painting, etc., complete.	R.ft.	170	
30	Finials large teakwood including fixing and painting.	No.	2	
31	Painting with silicate paint, two coats... ...	100 S.ft.	300	
32	Teakwood barge board	S.ft.	10	
33	Glass tiles	No.	10	
34	Providing cement boards on walls of waiting room with borders, etc., complete.	Lump sum		
35	Railway freight for gate and railing	Lump sum		
36	Teakwood benches 6 feet long	No.	2	
37	Levelling ground	Lump sum		

V. RAMANJULU NAIDU,
Executive Engineer,
Mysore Railways, Hassan.